



F.no-IIIT-D/Bldg Proj/Boundary Wall /263/2018

Dated : 11.10.2019

SPOT QUOTATION

Sealed item rate quotations are invited in one envelop system for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **Concertina Civil Works at IIITD Campus**, so as to reach the office of the undersigned upto 3PM on **14th Oct 2019** to be opened on the same day at 3:00 PM, in the office of the CE, A-201 2nd Floor of Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
2. **Time Allowed:** 10 days from issue of work order.
3. Schedule of quantity: As per enclosed BOQ. To be filled in neat handwriting.
4. Clause 12 of GCC CPWD is applicable for EI/SI.
5. Contractor must visit site before quoting and fully satisfy himself of the site conditions.
6. Contractor must possess valid GST, PAN, and TIN no.
7. No T&P shall be issued to the Contractor .The contractor shall be provided with electricity and water at one point ,he shall make his own arrangements for further distribution of electricity , water supply and all other labour, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.
8. The priced bill of quantities, all duly signed by the authorized signatory of the firms.
9. Payment shall be made as per actual quantities of executed works against running advance/Final bill.
10. Conditional offers will not be accepted. The offer shall remain valid for 30days.
11. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.
12. Contractor should depute a qualified supervisor dedicated for this work, who will monitor and coordinate work from contractor's side and interact with the IIITD Engineers, responsible for supervision of work, on regular basis.
13. Contractor will take due permission for entry of all his workers in IIITD. No unauthorized person will be allowed to work inside.
14. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.

CE

**BOQ for Concertina Civil Works**

S.no	Description	Qty	Unit	Rate	Amount
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	275	Kg		
2	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	100	RM		
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with.	2.5	cum		
	Cement mortar 1:6 (1 cement : 6 coarse sand)				
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:				
	1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	2	cum		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	Two or more coats on new work	30	Sqm		
6	Removal of old concertina coil outside the campus.	1	L/s		
	Total Amount				
	GST @ ___%				
	Total Amount with GST				

sIn words (Rs)

(_____)